

**Konstrukcja stalowa zadaszania trybuny stadionu – trybuna północna
(magazyn Radom – transport do 10 km)**

Wykaz elementów wykonanych - trybuna północna				
Symbol	Nazwa elementu	sztuk	Masa 1 elementu (kg/szt)	Masa całości
D2-01	D2-01	3	4344,2	13033
D2-02	D2-02	3	4364,3	13093
D2-03	D2-03	1	4343,6	4344
D2-04	D2-04	1	4398,4	4398
D2-05	D2-05	1	4359,8	4360
D2-06	D2-06	1	4359,8	4360
D2-07	D2-07	1	4383,7	4384
D2-08	D2-08	1	4363,8	4364
D2-09	D2-09	1	4361,3	4361
D2-10	D2-10	1	4384	4384
D2-11	D2-11	1	4345,6	4346
D2A-01	D2A-01	1	4257,3	4257
D2A-02	D2A-02	1	4257,3	4257
D2B-01	D2B-01	1	3462,8	3463
D2B-02	D2B-02	1	3468,7	3469
D3B-01	D3B-01	1	3086,9	2087
D3B-02	D3B-02	1	3087,6	3088
D4-01	D4-01	1	4190,1	4190
D4-02	D4-02	1	4160,9	4161
D4-03	D4-03	1	4190,1	4190
D4-04	D4-04	1	4160,3	4160
LP3-01	LP3-01	7	340,5	2384
LP4-01	LP4-01	1	342,6	343
LP4-02	LP4-02	1	342,6	343
L-ST-01	L-ST-01	36	40,4	1454
L-ST-02	L-ST-02	2	24,8	50
L-ST-03	L-ST-03	2	40,2	80
L-ST-04	L-ST-04	2	44,1	88
L-ST-05	L-ST-05	2	40,6	81
L-ST-06	L-ST-06	2	44,1	88
L-ST-07	L-ST-07	2	24,8	50
PL1-01	PL1-01	56	359,7	20141
PL1-09	PL1-09	2	158,9	318
PL1-10	PL1-10	2	178,7	357
PL1-11	PL1-11	2	199,5	399
PL1-12	PL1-12	2	240,4	481
PL1-13	PL1-13	2	305,8	612
PL1-14	PL1-14	2	371,2	742
PL1-15	PL1-15	2	49,4	99
PL1-16	PL1-16	8	178,9	1431
PL1-17	PL1-17	2	195	390
PL1-18	PL1-18	2	48,8	98
ST1-01	ST1-01	12	41,1	493

ST1-02	ST1-02	2	27	54
ST1-05	ST1-05	4	38,9	156
ST2-04	ST2-04	6	37,7	226
ST2-05	ST2-05	3	32,4	97
ST2-10	ST2-10	3	32,4	97
ST2-11	ST2-11	6	48,5	291
ST2-12	ST2-12	6	48,2	289
ST2-13	ST2-13	4	38,1	152
ST2-14	ST2-14	4	39,6	159
SW1-01	SW1-01	25	21,7	542
SW1-02	SW1-02	25	11,7	292
SW2-01	SW2-01	25	7,7	191
SW3-01	SW3-01	72	0,9	66
SW3-02	SW3-02	24	1,2	28
SW4-01	SW4-01	25	11,4	285
T1-01	T1-01	16	483,6	7738
T1-02	T1-02	1	618,1	618
T1-03	T1-03	1	130	130
T1-04	T1-04	2	474,5	949
T1-05	T1-05	1	583,1	583
T1-06	T1-06	1	583,1	583
T1-07	T1-07	1	133,8	134
T1-08	T1-08	1	133,8	134
T1-12	T1-12	1	480,7	481
T1-13	T1-13	1	480,7	481
T1-15	T1-15	1	130	130
T1-16	T1-16	16	618	618
T1A-01	T1A-01	1	710,4	11367
T1A-02	T1A-02	2	709,1	709
T1A-03	T1A-03	1	710,2	1420
T1A-04	T1A-04	28	709,1	709
T2-01	T2-01	1	82,6	2312
T2-02	T2-02	4	29,1	29
T2-03	T2-03	4	82,6	331
T2-04	T2-04	2	60,4	242
T2-05	T2-05	2	60,4	121
T2-06	T2-06	2	60,4	121
T2-07	T2-07	6	70,9	426
T2-10	T2-10	4	83,4	334
T2-14	T2-14	2	70,7	141
T2-15	T2-15	1	64,4	64
T2C-01	T2C-01	3	65,4	196
T2C-02	T2C-02	3	65,4	196
T2D-01	T2D-01	3	262	786
T3-01	T3-01	12	99,9	1199
T3-02	T3-02	2	58,3	117
T3-06	T3-06	4	105,7	423
T3A-01	T3A-01	4	106	424
T4-01	T4-01	10	220,1	2201

T4-02	T4-02	2	191,5	383
T4-03	T4-03	2	220,2	440
T4-04	T4-04	2	219,7	439
T5-01	T5-01	2	33	66
T5-02	T5-02	2	32,9	66
TB-02	TB-02	1	1713	1713

Uwaga: Zamawiający nie przekazuje Wykonawcy poniższych elementów według zestawienia, należy je wykonać na etapie montażu konstrukcji.

Brakujące elementy - trybuna północna				
Symbol	Nazwa elementu	sztuk	Masa 1 elementu (kg/szt)	Masa całości
BP1-01	BP1-01	25	372,3	9306
BP2-01	BP2-02	25	276,6	6688
L10-01	L10-01	2	245,9	492
L1-01	L1-01	36	240,5	8657
L11-01	L11-01	2	118,9	238
L12-01	L12-01	2	229,3	459
L13-01	L13-01	2	118,8	238
L8-01	L8-01	2	246,1	492
L9-01	L9-01	2	223,2	446
LP-ST-04	LP-ST-04	14	-	-
LP-ST-05	LP-ST-05	2	-	-
LP-ST-06	LP-ST-06	2	-	-